6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates tendered must be specific:—Tenders with vague quotations, such as "as per market rates," will not be accepted.

Constructing an additional Laboratory in the compound of Lambourne House at Bangalore.

Items of work.	Per	Rate	Quantity	Cost
		Rs. a. p.		Rs.
Earthwork excavation and filling basement	C. yd.	...	186	
Chunam concrete	C. ft.	...	1,377	
Stone in chunam foundation and basement including bond stones at 6' apart.	"	...	5,001	
Burnt stone slabs R. D. 6" thick	S. ft.	...	1,574	
Burnt brick in mortar	C. ft.	...	6,182	
Archwork with wire cut bricks in chunam	"	...	78	
Pillars of wire cut bricks in chunam (1½'×1½') with bearing slab base, capital including painting and colourwashing.	No.	...	16	
Teakwood panelled doors with brass fittings highly finished including iron clamps.	S. ft.	...	198	
Teakwood sash windows with brass fittings	"	...	84	
Do glazed windows, complete	"	...	392	
Do rectangular ventilators	"	...	120	
Do circular do	"	...	25	
Steel trusses including hoisting, complete	No.	...	4	
Bed slabs below trusses including bolts, etc., complete ...	"	...	8	
Teakwood wrought and put up with wood oiling	C. ft.	...	217·27	
Pukka terrace roof	Sq.	...	0·75	
Roofing with 1st class Mangalore tiles on teak reepers, chunam borders, etc.	"	...	12·34	
Roofing with 1st class Mangalore tiles on teak reepers with ceiling tiles, chunam borders, etc.	Sq.	...	27·72	
Ridge tiles set in mortar	R. ft.	...	115	
Valley gutters over ½" plank 3' wide zinc sheet, complete, including cement plastering and edges, etc.	"	...	15	
Teakwood ornamental eave board 1' deep with painting	"	...	371	
Cornice 9" deep all round verandah room	"	...	28	
Teakwood turned finials	No.	...	2	
Do down pendants	"	...	11	
Parapet wall 3' high	R. ft.	...	24	
Chunam plastering	Sq.	...	93·63	
White and colourwashing	"	...	43·43	
Calcarium washing	"	...	48·54	
Dado painting with calcarium	R. ft.	...	280	
Silicate painting	Sq.	...	13·48	
Flooring with Cuddapah slabs over 3" concrete including cement pointing.	"	...	11·52	
Flooring with acid proof tiles on 3" concrete and cement pointing ...	"	...	4·80	
Flooring with Mangalore square tiles	"	...	7·00	
Constructing flights of steps opening a door way to museum and constructing a flue with fire-bricks, casing in fire clay.	L. S. Rs.	...	...	200
Chunam pointing to basement	Sq.	...	9·00	
Fixing a water basin in verandah room and drainage arrangement	L. S. Rs.	...	...	200
Rolled steel joists 4½"×1½" seet at 6½ lbs. per R. ft. ...	Cwts.	...	4·17	
Providing and fixing an iron water tank 6' Dr.×3' height with a light cover of corrugated iron on S. M. Rails placed on bed slabs (1½'×1½'×6") etc.	L. S. Rs.	...	...	400

C. VIJAYARANGAM NAIDU,
Executive Engineer.

KOLAR DIVISION.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, pages 698—699, calling for tenders for restoring Suranahalli tank, Regd. No. 174 of Bowringpet Taluk.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 699, calling for tenders for constructing a compound wall around the special lock-up at Champion Reefs, Kolar Gold Fields.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 697, calling for tenders for constructing the A.-V. School at Bagepalli.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*,

782

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette* dated 1st August 1918, Part IV, page 721, calling for tenders for restoring Ternahalli Cholaghattadakere tank, registered No. 479 of Kolar Taluk.

Dated 5th August 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 12 noon on 5th September 1918, for restoring Ghatti Madamangala tank, Registered No. 602 of Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Ghatti Madamangala tank, Registered No. 602 of Bowringpet Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for restoring Ghatti Madamangala tank, Registered No. 602 of Bowringpet Taluk.

Items of work	Per	Quantity
Bund—		
1. Earthwork watering and tamping	C. yd.	3,588
2. Cutting grips, etc.	Lump	sum
3. Turfing	S. yd.	4,036
4. Removing and resetting old stones work with new jelly	C. yd.	413
5. New stone work	"	1,420
6. New grade stones with index stone including painting and numbering	No.	17
7. New registered number and date stone	"	2
8. New gauge stone with painting and numbering	"	1
9. New B. M. stones do do	"	3
10. Cutting bund tracing leaks	Lump	sum
Left waste weir—		
1. Dismantling top portion of body wall	Lump	sum
2. Burnt brick in surki mortar	C. ft.	1,892
3. Burnt stone slabs	S. ft.	254
4. Removing and resetting old stones with new jelly	C. yd.	347
5. Plastering with surki mortar	Sq.	213·65
6. Earthwork excavation	C. yd.	24
7. Surki concrete	C. ft.	113
8. Cement plastering	Sq.	4·00
Right waste weir—		
1. Benching rock	"	92
2. Burnt brick in surki mortar	C. ft.	175
3. Burnt stone slabs	S. ft.	73
4. Surki mortar plastering	Sq.	2·58
5. Rough stone work, new	C. yd.	20
No. 2, sluice—		
Constructing No. 2 sluice with cistern and walls—		
1. Earthwork cutting and refilling with watering and tamping	C. yd.	241
2. Earthwork excavation	"	23
3. Concrete in surki mortar	C. ft.	189
4. Burnt brick in surki mortar	"	627
5. Burnt stone slabs	S. ft.	405
6. Plastering with surki mortar	Sq.	300
7. Dismantling and removing old sluice	Lump	sum
8. Baling water	Do	Do
9. Ring bund	Do	Do

V. V. KARVE,
Executive Engineer.